

VICINITY MAP

SITE LOCATION MAP

PHASE IIIB 8-INCH GRAVITY WASTEWATER LINE IMPROVEMENTS

TO SERVE THE

± 463-ACRE MID-CAROLINA COMMERCE PARK NEWBERRY COUNTY, SOUTH CAROLINA





SHEET INDEX

SHEET NO	SHEET
C0.0	COVER SHEET
C1.0	OVERALL EXISTING CONDITIONS AND STANDARD NOTES
C2.0	CLEARING, GRUBBING, AND DEMOLITION PLAN
C3.0	OVERALL GRAVITY WASTEWATER UTILITY PLAN
C3.1	GRAVITY WASTEWATER UTILITY PLAN AND PROFILE STA: 0+00 TO 14+00
C3.2	GRAVITY WASTEWATER UTILITY PLAN AND PROFILE STA: 14+00 TO 28+00
C3.3	GRAVITY WASTEWATER UTILITY PLAN AND PROFILE STA: 28+00 TO 38+50
C3.4	TRANSMISSION LINE EASEMENT EXHIBIT
C4.0	EROSION AND SEDIMENT CONTROL PLAN STA: 0+00 TO 14+00
C4.1	EROSION AND SEDIMENT CONTROL PLAN STA: 14+00 TO 35+00
C5.0	EROSION AND SEDIMENT CONTROL DETAILS
C6.0	WASTEWATER DETAILS



CAUTION-NOTE TO CONTRACTOR

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND. WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD, THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. SC LAW REQUIRES THE CONTRACTOR TO CALL THE UTILITY PROTECTION CENTER AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE RELOCATION OF ALL THE UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

NEWBERRY COUNTY COUNCIL:

MR. NICK SHEALY, CHAIRMAN MR. KARL SEASE, VICE-CHAIRMAN

MR. LEON FULMER JR. MR. TODD JOHNSON

MR. TRAVIS REEDER MR. JOHNNY MACK SCURRY MR. STUART SMITH

RAILROAD INVOLVEMENT? YES / NO

GAS TRANSMISSION INVOLVEMENT? YES / NO

NPDES PERMIT INFORMATION

NPDES DISTURBED AREA = 3.8 ACRES

DEVELOPER INFORMATION CENTER:

EMAIL:

OWNER: NEWBERRY COUNTY ECONOMIC DEVELOPMENT CONTACT: RICK FARMER, SCCED, DIRECTOR ADDRESS: 1852 WILSON ROAD CITY, STATE: NEWBERRY, SOUTH CAROLINA 29108

TELEPHONE: (803) 321-2042 RFARMER@NEWBERRYCOUNTY.NET **ENGINEER INFORMATION:**

ALLIANCE CONSULTING ENGINEERS, INC. BENJAMIN S. WHALEY, P.E. POST OFFICE BOX 8147 CITY, STATE: COLUMBIA, SOUTH CAROLINA 29202 TELEPHONE: (803) 779-2078

SWHALEY@ALLIANCECE.COM

NATURAL GAS PROVIDER: CONTACT: MR. STAN BRYSON, GENERAL MANAGER CLINTON-NEWBERRY NATURAL GAS AUTHORITY TELEPHONE: (803) 276-1550 FAX: (803) 276-9096

TELEPHONE: (803) 276-7020

TELEPHONE: (803) 276-1121

UTILITY PROVIDER CONTACTS
WATER AND WASTEWATER PROVIDER:
CONTACT: MR. DANIEL QUATTLEBAUM

OPERATIONS

FAX: (803) 276-4121


ELECTRICAL UTILITY PROVIDER:


TELECOMMUNICATIONS PROVIDER: CONTACT: MR. IKE BYRD, REGIONAL DIRECTOR EXTERNAL AFFAIRS AT&T SOUTH CAROLINA TELEPHONE: (803) 401-2214 FAX: (803) 765-2674

CONTACT: MR. JASON MERCHANT, MANAGER OF ENGINEERING AND

NEWBERRY ELECTRIC COOPERATIVE, INC.

NEWBERRY COUNTY WATER AND SEWER AUTHORITY










FEBRUARY 2025


Project No. 25105-0036


DWG NO. 01,1722-D30



























DWG NO.01,1722-D30






SILT FENCE ROCK OUTLET TOP OF FENCE FACE ON UPSTREAM SIDE **ELEVATION - UP-SLOPE FACE** 6" MIN. THICKNESS

FILTER FABRIC

MATERIAL

RUNOFF



South Carolina Department of Health and Environmental Control

3 FT.


18-IN.

-18" MULCH

SILT FENCE ROCK OUTLET STANDARD DRAWING NO. SC-14 PAGE 1 of 1 NOT TO SCALE FEBRUARY 2014

DATE

- 1. WASHED STONE (#57) TO BE REMOVED AND REPLACED ONCE IT BECOMES
- 2. SEDIMENT TO BE REMOVED WHEN ACCUMULATIONS REACH 1/3 HEIGHT OF SILT
- 3. THE KEY TO FUNCTIONAL ROCK OUTLETS IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.



- PREPARE SOIL BEFORE INSTALLING ROLLED EROSION CONTROL PRODUCT (RECPs), INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. NOTE: WHEN USING CELL-O-SEED, DO NOT SEED PREPARED AREA. CELL-O-SEED MUST BE INSTALLED WITH
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE RECPS IN A 6" (15CM) DEEP X 6" (15CM) WIDE TRENCH WITH APPROXIMATELY 12" (30CM) OF RECPS EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE RECPS WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30CM) APART IN THE BOTTOM OF THE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING, APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30CM) PORTION OF RECPS BACK OVER SEED AND COMPACTED SOIL. SECURE RECPS OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30CM) APART ACROSS THE WIDTH OF THE
- ROLL THE RECPS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. RECPS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL RECPS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING THE DOT SYSTEM™, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
- THE EDGES OF PARALLEL RECPS MUST BE STAPLED WITH APPROXIMATELY 2"-5" (5CM-12.5CM) OVERLAP DEPENDING ON RECP TYPE. CONSECUTIVE RECPS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5CM) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30CM) APART ACROSS ENTIRE RECP WIDTH.

NOTE: IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15CM) MAY BE NECESSARY TO PROPERLY SECURE THE RECPS.

> SLOPE INSTALLATION DETAIL PROVIDED BY NORTH AMERICAN GREEN NOT TO SCALE

FILE NAME: SHEET C5.0.DWG REFERENCE FILE 25105-0036 C5.0 Base.dwg

PROJECT NO. 25105-0036 DWG NO. 01,1722-D30

Sediment and Erosion Control Notes

- 1. If necessary, slopes, which exceed eight (8) vertical feet should be stabilized with synthetic or vegetative mats, in addition to hydroseeding. It may be necessary to install temporary slope drains during construction. Temporary berms may be needed until the slope is brought to grade.
- 2. Stabilization measures shall be initiated as soon as practicable in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than fourteen (14) days after work has ceased, except as stated below. > Where stabilization by the 14th day is precluded by snow cover or frozen ground conditions stabilization measures must be initiated as soon as practicable.
- > Where construction activity on a portion of the Site is temporarily ceased, and earth-
- disturbing activities will be resumed within fourteen (14) days, temporary stabilization
- measures do not have to be initiated on that portion of the Site.
- 3. All sediment and erosion control devices shall be inspected every seven (7) days. If site inspections identify BMPs that are damaged or are not operating effectively, maintenance must be performed as soon as practical or as reasonably possible and before the next storm event whenever practicable.
- 4. Provide silt fence and/or other control devices, as may be required, to control soil erosion during utility construction. All disturbed areas shall be cleaned, graded, and stabilized with grassing immediately after the utility installation. Fill, cover, and temporary seeding at the end of each day are recommended. If water is encountered while trenching, the water should be filtered to remove any sediments before being pumped back into any waters of the State.
- 5. All erosion control devices shall be properly maintained during all phases of construction until the completion of all construction activities and all disturbed areas have been stabilized. Additional control devices may be required during construction in order to control erosion and/or offsite sedimentation. All temporary control devices shall be removed once construction is complete and the site is stabilized.
- 6. The contractor must take necessary action to minimize the tracking of mud onto paved roadway(s) from construction areas and the generation of dust. The contractor shall daily remove mud/soil from pavement, as may be required.
- 7. Residential subdivisions require erosion control features for infrastructure as well as for individual lot construction. Individual property owners shall follow these plans during construction or obtain approval of an individual plan in accordance with S.C Reg. 72-300 et seq. and SCR100000.
- 8. Temporary diversion berms and/or ditches will be provided as needed during construction to protect work areas from upslope runoff and/or to divert sediment-laden water to appropriate traps or stable outlets. 9. All waters of the State (WoS), including wetlands, are to be flagged or otherwise clearly marked in the field. A double row of silt fence is to be installed
- in all areas where a 50-foot buffer can't be maintained between the disturbed area and all WoS. A 10-foot buffer should be maintained between the 10.Litter, construction debris, oils, fuels, and building products with significant potential for impact (such as stockpiles of freshly treated lumber) and
- construction chemicals that could be exposed to storm water must be prevented from becoming a pollutant source in storm water discharges. 11.A copy of the SWPPP, inspections records, and rainfall data must be retained at the construction site or a nearby location easily accessible during
- normal business hours, from the date of commencement of construction activities to the date that final stabilization is reached. 12.Initiate stabilization measures on any exposed steep slope (3H:1V or greater) where land-disturbing activities have permanently or temporarily ceased, and will not resume for a period of seven (7) calendar days.
- 13. Minimize soil compaction and, unless infeasible, preserve topsoil. 14. Minimize the discharge of pollutants from equipment and vehicle washing, wheel wash water, and other wash waters. Wash waters must be treated
- in a sediment basin or alternative control that provides equivalent or better treatment prior to discharge; 15.Minimize the discharge of pollutants from dewatering of trenches and excavated areas. These discharges are to be routed through appropriate BMPs (sediment basin, filter bags, etc.).
- 16. The following discharges from sites are prohibited:
 - Wastewater from washout of concrete, unless managed by an appropriate control;
 - Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds, and other construction materials; - Fuels, oils, or other pollutants used in vehicle and equipment operation and maintenance; and - Soaps or solvents used in vehicle and equipment washing.
- 17. After construction activities begin, inspections must be conducted at a minimum of at least once every calendar week, with no time period between inspections exceeding 9 days, and must be conducted until final stabilization is reached on all areas of the construction site. It is recommended that BMPs be assessed by the contractor within 24 hours of the end of a storm event of 1.0 inch or greater, as well as during the first rain event after the initiation of construction activities, after the installation of BMPs.
- 18.If existing BMPs need to be modified or if additional BMPs are necessary to comply with the requirements of this permit and/or SC's Water Quality Standards, implementation must be completed before the next storm event whenever practicable. If implementation before the next storm event is impracticable, the situation must be documented in the SWPPP and alternative BMPs must be implemented as soon as reasonably possible. 19. A Pre-Construction Conference must be held for each construction site with an approved On-Site SWPPP prior to the implementation of construction activities. For non-linear projects that disturb ten (10) acres or more, this conference must be held on-site unless the Department has approved otherwise.

- A. Install permanent vegetative cover and the long-term erosion protection measures or structures as soon as practical in the development process.
- B. Provide for handling the increased runoff caused by changed soil and surface conditions. Use effective means to conserve existing on-site soil including the use of diversion ditches, grassed waterways
- C. Place silt fence barriers at locations shown on plan. Silt barriers shall be maintained in place and in good condition until ground cover is established.

NOTES:

- D. All disturbed areas not paved shall be grassed. Use temporary plant cover, mulching, and/or
- structures to control runoff and protect areas subject to erosion during construction.
- E. Sediment ponds are to be excavated to original grades upon the accumulation of 1.5' on sediment stake placed at outlet. F. Provide a temporary stone splash pad at all fire hydrants or other points if discharge during testing
- of the water distribution system.
- G. Should Permanent Grassing requirements conflict with Landscape Plans, Landscape Plans supercede Permanent Grassing requirments.

Grassing Specifications:

on all bank slopes less than 3:1.

A. All seed mixtures for the various seeding schedules shall be weighed and mixed to the proper

proportions in the presence of the owner or the owner's representative.

PERMANENT SEEDING Maintained Turf (High Profile Lawn/Landscaped Areas) Planting Dates Application Rate Slopes 4H:1V or Greater Planting Dates Slopemaster Spring/Summer Mix by Pennington Seeding, Inc Slopemaster Spring/Summer Mix Composition 25% Hulled Sahara Bermudagrass 25% Unhulled Sahara Bermudagrass 25% Pensacola Bahiagrass 10% Durana White Clover 10% Brown Top Millet 5% Weeping Lovegrass September 15 - March 31 Slopemaster Fall/Winter Mix by Pennington Seed, Inc. 100 LBS/ACRE Slopemaster Fall/Winter Mix Composition 25% Unhulled Sericea Lespedeza 20% Unhulled Sahara Bermudagrass 20% Greystone Tall Fescue 10% Durana White Clover 10% Rye Grain 5% Weeping Lovegrass Slope 4H:1V or Less Application Rate Hulled Sahara Bermudagrass

September 15 - March 31 Unhulled Sahara Bermudagrass 100 LBS/ACRE


Vennington Seed, Inc. - 1236 Eden Street, Columbia, SC 29201 - Jay Sprague - (803) 608-5963 B. Double seed all grassed swales , water ways, and embankments from top of bank to bottom of bank

CONSTRUCTION SEQUENCE

- 1. RECEIVE NPDES COVERAGE FROM SCDES.
- 2. NOTIFY SCDES REGIONAL OFFICE 48 HOURS PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- 3. CLEARING AND GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS. (E.G., SILT FENCE AND CONSTRUCTION ENTRANCE).

DOUBLE SILT FENCE

- 4. INSTALL PERIMETER EROSION AND SEDIMENT CONTROL DEVICES.(SILT FENCE AND CONSTRUCTION ENTRANCE)
- 5. CLEARING AND GRUBBING OF SITE AS NECESSARY TO INSTALL ALL EROSION AND SEDIMENT CONTROL MEASURES IN THESE AREAS.
- 6. EXCAVATION OF TRENCH AND KEEP SOIL IN TEMPORARY CONSTRUCTION EASEMENT.
- 7. USE DOUBLE ROW OF SILT FENCE ON DOWNSTREAM SIDE OF WASTEWATER INSTALLATION WHERE GRADING APPROACHES EDGE OF WETLAND BUFFER.
- B. INSTALL GRASSING ALONG CLEARING LIMITS ONCE TRENCHING AND BACKFILL IS COMPLETED. TEMPORARY GRASSING WILL NEED TO BE PLACED ALONG TRENCH
- BEFORE 14 DAYS OF COMPLETION OF WASTEWATER LINE. 9. INSTALL PERMANENT GRASSING ONCE ALL IS INSTALLED.
- 10. MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES FOR THE EXTENT OF THE
- 11. ONCE THE SITE STABILIZES, REMOVE TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER ENTIRE AREA DRAINING TO THE STRUCTURE IS FINALLY STABILIZED (SCDES RECOMMENDS THAT THE PROJECT OWNER/OPERATOR HAVE THE SWPPP PREPARER (IF APPLICABLE) OR REGISTRATION EQUIVALENT APPROVE THE REMOVAL OF THE TEMPORARY STRUCTURES).



WHEN AND WHERE TO USE IT

STABILIZED CONSTRUCTION ENTRANCES SHOULD BE USED AT ALL POINTS WHERE TRAFFIC WILL BE LEAVING A CONSTRUCTION SITE AND MOVING DIRECTLY ONTO A PUBLIC ROAD.

IMPORTANT CONSIDERATIONS

IF WASHING IS USED, PROVISIONS MUST BE MADE TO INTERCEPT THE WASH WATER AND TRAP THE SEDIMENT BEFORE IT IS CARRIED OFFSITE. WASHDOWN FACILITIES SHALL BE REQUIRED AS DIRECTED BY SCOHEC AS NEEDED. WASHDOWN AREAS IN GENERAL MUST BE ESTABLISHED WITH CRUSHED GRAVEL AND DRAIN INTO A SEDIMENT TRAP OR SEDIMENT BASIN.

CONSTRUCTION ENTRANCES SHOULD BE USED IN CONJUNCTION WITH THE STABILIZATION OF CONSTRUCTION ROADS TO AMOUNT OF MUD PICKED UP BY VEHICLES.

REMOVE ALL VEGETATION AND ANY OBJECTIONABLE MATERIAL FROM THE FOUNDATION AREA.

DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM STONES TO A SEDIMENT TRAP OR BASIN. INSTALL A NON-WOVEN GEOTEXTILE FABRIC PRIOR TO PLACING ANY STONE INSTALL A CULVERT PIPE ACROSS THE ENTRANCE WHEN NEEDED TO PROVIDE POSITIVE DRAINAGE.

THE ENTRANCE SHALL CONSIST OF 1-INCH TO 3-INCH D50 STONE PLACED AT A MINIMUM DEPTH OF 6-INCHES. MINIMUM DIMENSIONS OF THE ENTRANCE SHALL BE 24-FEET WIDE BY 100-FEET LONG, AND MAY BE MODIFIED AS NECESSARY TO ACCOMMODATE SITE CONSTRAINTS

THE EDGES OF THE ENTRANCE SHALL BE TAPERED OUT TOWARDS THE ROAD TO PREVENT TRACKING OF MUD AT THE EDGE OF THE ENTRANCE.

INSPECT CONSTRUCTION ENTRANCES EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES ½-INCHES OR MORE OF PRECIPITATION, OR AFTER HEAVY USE. CHECK FOR MUD AND SEDIMENT BUILDUP AND PAD INTEGRITY. MAKE DAILY INSPECTIONS DURING PERIODS OF WET WEATHER. MAINTENANCE IS REQUIRED MORE FREQUENTLY IN WET WEATHER CONDITIONS. RESHAPE THE STONE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL WASH OR REPLACE STONES AS NEEDED AND AS DIRECTED BY THE INSPECTOR. THE STONE IN THE ENTRANCE SHOULD BE

WASHED OR REPLACED WHENEVER THE ENTRANCE FAILS TO REDUCE MUD BEING CARRIED OFF-SITE BY VEHICLES. FREQUENT WASHING WILL EXTEND THE USEFUL LIFE OF STONE. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. FLUSHING SHOULD ONLY BE USED WHEN THE WATER CAN BE DISCHARGED TO A SEDIMENT TRAP OR BASIN. REPAIR ANY BROKEN PAVEMENT IMMEDIATELY.

STABILIZED CONSTRUCTION ENTRANCE (SCDHEC DETAIL SC-06)

